

URAIAN SINGKAT PEKERJAAN

NO	URAIAN PEKERJAAN	SAT	VOLUME
B. PEKERJAAN TANAH			
1.	Pek. Galian Jalur Pipa Ø 75 mm	M3	111,00
2.	Pek. Galian Jalur Pipa Ø 50 mm	M3	63,00
3.	Pek. Galian Jalur Pipa Ø 25 mm	M3	30,00
4.	Pek. Urugan Pasir (Pelindung Badan Pipa)	M3	57,90
5.	Pek. Penimbunan Tanah Kembali Bekas Galian Pipa	M3	114,00
C. PENGADAAN & PEMASANGAN PIPA DAN AKSESORIS JARINGAN			
1.	Pipa PVC Ø 75 mm S 12.5	M1	740,00
2.	Pipa PVC Ø 50 mm S 12.5	M1	420,00
3.	Pipa HDPE Ø 25 mm	M1	200,00
4.	Bend 90 PVC Ø 75 mm	Bh	2,00
5.	Bend 90 PVC Ø 50 mm	Bh	5,00
6.	Baut mur 5/8 x 6 cm	Psg	6,00
7.	Stop kran PVC Ø 50 mm	Bh	1,00
8.	Tee PVC Ø 75 x 50 mm	Bh	1,00
D. PENGADAAN & PEMASANGAN PIPA INLET DAN OUTLET TOWER			
1.	Pipa GIP Ø 50 mm	M1	30,00
2.	Pipa HDPE Ø 50 mm	M1	70,00
3.	Bend GIP 90 Ø 50 mm	Bh	3,00
4.	Bend GIP 45 Ø 50 mm	Bh	2,00
5.	Butterfly Valve Ø 50 mm	Bh	1,00
6.	Flange Steel Ø 50 mm	Bh	9,00
7.	Flange Spigot Ø 50 mm	Bh	1,00
8.	Baut mur 5/8 x 6 cm	Psg	48,00
E. PENGADAAN & PEMASANGAN FLOW METER Ø 75 mm			
1.	Water Meter SNI Ø 75 mm	Bh	1,00
2.	Pipa GIP Ø 75 mm	M1	6,00
3.	Flange Steel Ø 75 mm	Bh	2,00
4.	Gate Valve Ø 75 mm	Bh	1,00
5.	Flange Spigot Ø 75 mm	Bh	2,00
6.	Karet Packing Ø 75 mm	Bh	3,00
7.	Bend GIP Ø 75 mm	Bh	4,00
8.	Baut mur 5/8 x 6 cm	Psg	18,00
9.	Manhole Meter Induk	Ls	1,00
F. PENGADAAN & PENGOPELAN PIPA EKSISTING DAN ANTAR GEDUNG			
1.	Pipa PVC Ø 75 mm S 12.5	M1	6,00
2.	Tee PVC Ø 75 x 75 mm	Bh	1,00
3.	Stop kran PVC Ø 75 mm	Bh	1,00
4.	Water Mur Ø 25 mm	Bh	10,00
5.	TBA Jumbo	Bh	5,00
6.	Lem PVC	Klg	2,00
7.	Pengopelan ke pipa eksisting Ø 75 mm	Ttk	1,00
8.	Pengopelan pipa antar gedung	Ttk	6,00